SITE CONSTRUCTION PLANS

PONDEROSA WOODS STREAM RESTORATION PROJECT

Project Team

CITY OF PLYMOUTH **BEN SCHARENBROICH - WATER RESOURCES SUPERVISOR** 3400 PLYMOUTH BLVD PLYMOUTH, MN 55447 PHONE - (763) 509-5527

LANDSCAPE ARCHITECT: MIDWEST WETLAND IMPROVEMENTS, LLC LUCIUS JONETT, PLA P.O. BOX 448 VICTORIA, MN 55386 MOBILE - (952) 261-9990

CIVIL ENGINEER: CIVIL METHODS, INC. KENT BRANDER, PE P.O. BOX 28038 ST. PAUL, MN 55128 MOBILE - (612) 819-6581

SURVEYOR: ANDERSON ENGINEERING OF MN NICK HILLMER, PS 13605 FIRST AVENUE NORTH PLYMOUTH, MN 55441 MOBILE - (763) 370-1582

NOT TO SCALE

PROJECT LOCATION CITY: PLYMOUTH COUNTY: HENNEPIN



FOR

CITY PROJECT # WR210003 PLYMOUTH, MN



P.O. BOX 448 VICTORIA, MN 55386 PHONE: (952) 261-9990 WWW.MIDWESTWETLANDS.C

CERTIFICATION

SPECIFICATION OR REPORT WA PARED BY ME OR UNDER M LY LICENSED PROFESSIONA NDSCAPE ARCHITECT UNDER

ICENSE NO .: 10-31-20 DATE: _____

AM Ш Ш ()S \bigcap MOO TION PONDEROSA RESTORA⁻ CLIENT: Plymouth 3400 PLYMOUTH BLVD PLYMOUTH, MN 55447

PHONE: 763-509-5000 WWW.PLYMOUTHMN.COM						
PROJECT NO.: 0017-03						
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ				
SSUE DATE)/30/2024					
SSUE NO.: 02						
HEET TITLE:						
COVER SHEET						

G-101

SHEET NO .:

DRAWING INDEX							
Sheet Number	Sheet Title						
G-101	COVER SHEET						
G-102	CONSTRUCTION NOTES						
EC-101	SWPPP						
C-101	SITE ACCESS AND BUCKTHORN TREATMENT						
C-102	TREE REMOVALS 1						
C-103	TREE REMOVALS 2						
C-104	TREE SURVEY - TREES SAVED						
C-105	TREE SURVEY - TREES REMOVED						
C-110	CHANNEL STABILIZATION PLAN 1						
C-111	CHANNEL STABILIZATION PLAN 2						
C-120	CHANNEL CROSS SECTIONS						
C-121	CHANNEL CROSS SECTIONS						
C-130	REVEGETATION PLAN 1						
C-131	REVEGETATION PLAN 2						
C-801	DETAILS						
C-802	DETAILS						
C-803	DETAILS						
C-804	DETAILS						



GOVERNING SPECIFICATIONS

- 1. CITY OF PLYMOUTH ENGINEERING GUIDELINES, STANDARD SPECIFICATIONS AND REQUIREMENTS.
- 2. MINNESOTA DEPARTMENT OF TRANSPORTATION (MN/DOT) "STANDARD SPECIFICATIONS FOR CONSTRUCTION" LATEST EDITION AND SUPPLEMENTS.
- 3. CITY ENGINEERS ASSOCIATION OF MINNESOTA (CEAM) STANDARD SPECIFICATIONS FOR UTILITIES LATEST EDITION.
- 4. APPLICABLE FEDERAL, STATE, AND LOCAL LAWS AND ORDINANCES

REMOVAL / DEMOLITION NOTES

- 1. SEE GENERAL NOTES FOR ADDITIONAL PROJECT AND SITE INFORMATION.
- 2. CONTRACTOR SHALL REVIEW FEATURES NOT SPECIFICALLY IDENTIFIED ON PLAN FOR SALVAGE OR REMOVAL THAT CONFLICT WITH CONSTRUCTION WITH THE ENGINEER.
- 3. MATERIALS REMOVED/DEMOLISHED BY CONTRACTOR BECOME PROPERTY OF THE CONTRACTOR, UNLESS OTHERWISE NOTED. CONTRACTOR SHALL LOAD AND HAUL MATERIAL OFF-SITE AND PROPERLY DISPOSE OF MATERIALS IN ACCORDANCE WITH APPLICABLE REGULATIONS. CONTRACTOR MUST LEAVE THE SITE IN A CONDITION TO THE SATISFACTION OF THE OWNER AND ENGINEER.
- 4. IN THE EVENT THAT UNKNOWN CONTAINERS OR TANKS ARE ENCOUNTERED. THE CONTRACTOR MUST CONTACT THE ENGINEER IMMEDIATELY. ALL CONTAINERS OR TANKS MUST BE DISPOSED OF PROPERLY AT A REGULATED/PERMITTED FACILITY.
- 5. CONTRACTOR SHALL REVIEW ALL TREE REMOVALS WITH THE OWNER AND LANDSCAPE ARCHITECT PRIOR TO REMOVAL OPERATIONS.
- CLEARING AND GRUBBING OPERATIONS MUST COMPLY WITH THE FOLLOWING:
- A. PROTECT ALL TREES AND PLANTS NOT DESIGNATED FOR REMOVAL.
- B. CONDUCT OPERATIONS IN SUCH A MANNER THAT DOES NOT DAMAGE PROTECTED TREES AND VEGETATION.
- C. CUT, REMOVE, AND DISPOSE OF TREES, BRUSH, SHRUBS, WINDFALLS, LOGS, STUMPS, ROOTS, FALLEN TIMBER, AND OTHER VEGETATION NOT DESIGNATED FOR HARVEST OR REUSE
- D. BACKFILL DEPRESSIONS WITH NATIVE SOILS OR SUITABLE FILL MATERIAL AS REQUIRED BY DESIGN OR AS DIRECTED BY THE LANDSCAPE ARCHITECT AND COMPACT BACKFILL AS DIRECTED.
- E. DISPOSE OF DEBRIS IN ACCORDANCE WITH APPLICABLE REGULATIONS.
- F. CONSIDER BENEFICIAL USE DESIGNATIONS FOR UNADULTERATED WOOD WOOD CHIPS. BARK AND SAWDUST.
- G. NO BURYING OF CLEARED AND GRUBBED WASTE WITHIN THE CONSTRUCTION LIMITS.

GENERAL NOTES

- 1. UNTIL REVISION BLOCK STATES "ISSUED FOR CONSTRUCTION", THE PLAN SET IS NOT CERTIFIED FOR CONSTRUCTION.
- 2. EXISTING CONDITIONS SHOWN ARE FROM A COMBINATION OF TOPOGRAPHIC SURVEY AND LIDAR DATA COMPLETED BY ANDERSON ENGINEERING OF MINNESOTA, DATED AUGUST 2024. CONTRACTOR RESPONSIBLE FOR VERIFYING THE CONDITIONS OF THE SITE AND MUST IMMEDIATELY NOTIFY THE ENGINEER OF DISCREPANCIES OR VARIATIONS FROM THE DRAWINGS.
- SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-2 ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA". EXACT LOCATION/DEPTH OF SUBSURFACE UTILITIES SUCH AS GAS, TELEPHONE, FIBER OPTIC, SEWER, WATER, PIPELINES, ELECTRICAL, AND CABLE TV ARE UNKNOWN AND THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE.
- 4. CONTRACTOR RESPONSIBLE FOR CONTACTING GOPHER STATE ONE CALL (1-800-252-1166) A MINIMUM OF 48 HOURS IN ADVANCE (EXCLUDING HOLIDAYS AND WEEKENDS) BEFORE STARTING WORK FOR LOCATIONS OF UNDERGROUND UTILITIES.

GENERAL NOTES - CONT.

- 5. CONTRACTOR SHALL ANTICIPATE PRIVATE UTILITY CONFLICTS THROUGHOUT THE PROJECT AREAS AND MUST COORDINATE THE RELOCATION OR PROTECTION OF EXISTING UTILITIES.
- 6. QUANTITIES ARE APPROXIMATE. AND MAY VARY TO ALLOW COMPLETION OF WORK.
- 7. PROTECTION OF ITEMS NOT CALLED OUT TO BE REMOVED SHALL BE INCIDENTAL.
- 8. WORK AND MATERIALS MUST COMPLY WITH CITY, COUNTY, STATE, AND FEDERAL (INCLUDING OSHA) REGULATIONS AND CODES.
- 9. CONTRACTOR SHALL COORDINATE AND MAINTAIN ACCESS TO ADJACENT PROPERTIES THROUGHOUT CONSTRUCTION.
- 10.CONTRACTOR SHALL COORDINATE AND MAINTAIN MAIL. GARBAGE. AND RECYCLING SERVICES TO PROPERTIES THROUGHOUT CONSTRUCTION.
- 11.CONSTRUCTION LIMITS ARE TO PROPERTY LINE UNLESS SHOWN OR NOTED OTHERWISE. CONTRACTOR SHALL RESTRICT CONSTRUCTION ACTIVITIES TO AREAS DESIGNATED ON PLANS WITHIN THE CONSTRUCTION LIMITS.
- 12.CONTRACTOR SHALL PRESERVE AND PROTECT EXISTING PAVEMENT, SITE FEATURES, UTILITIES, TREES, ETC., UNLESS NOTED OR SHOWN OTHERWISE.
- 13.EXISTING PAVEMENT AND SITE CONDITIONS HAVE BEEN DOCUMENTED. AND ANY DAMAGE TO THE EXISTING PAVEMENT, CURBING, STRIPING, OR OTHER SITE FEATURE TO REMAIN MUST BE REPLACED BY THE CONTRACTOR. TO OWNER'S SATISFACTION, AT NO ADDITIONAL COST TO THE OWNER.
- 14.CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO AVOID PROPERTY DAMAGE TO ADJACENT PROPERTIES DURING CONSTRUCTION AND WILL BE HELD SOLELY RESPONSIBLE FOR ANY DAMAGES.
- 15.CONTRACTOR MUST IMMEDIATELY NOTIFY THE OWNER AND ENGINEER OF DISCREPANCIES OR CONFLICTS IN THE CONTRACT DOCUMENTS BEFORE COMMENCING WORK. NO FIELD CHANGES OR DEVIATIONS ARE TO BE MADE WITHOUT PRIOR APPROVAL FROM THE OWNER AND ENGINEER. FAILURE TO NOTIFY OWNER AND ENGINEER OF AN IDENTIFIABLE CONFLICT BEFORE PROCEEDING WITH INSTALLATION RELIEVES OWNER OF ANY OBLIGATION TO PAY FOR A RELATED CHANGE ORDER.
- 16.CONTRACTOR SHALL HAVE ONE COPY OF EACH REQUIRED CONSTRUCTION PERMIT AND ONE COPY OF THE MOST CURRENT AND COMPLETE SET OF CONSTRUCTION DOCUMENTS (INCLUDING PLANS, SPECIFICATIONS, GEOTECHNICAL REPORT, SPECIAL CONDITIONS AND PROVISIONS, ETC.) AVAILABLE AT THE PROJECT SITE AT ALL TIMES.
- 17.CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR IMPLEMENTATION AND ENFORCEMENT OF SAFE WORK PRACTICES. INCLUDING BUT NOT LIMITED TO PERSONNEL MONITORING, USE OF TRENCHING, SHEETING, AND SHORING. SCAFFOLDING: MATERIALS HANDLING AND DRILLING: OPERATION OF EQUIPMENT; AND SAFETY OF PUBLIC DURING PROGRESS OF WORK.
- 18.CONTRACTOR SHALL PLAN FOR AND ENSURE PERSONNEL COMPLY WITH PROVISIONS OF OSHA SAFETY AND HEALTH STANDARDS (29 CFR 1910) AND GENERAL CONSTRUCTION STANDARDS (29 CFR 1926) AS APPROPRIATE.
- 19.CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH WORK. CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS FOR SAFETY OF EMPLOYEES ON PROJECT SITE AND OTHER PERSONS AND ORGANIZATIONS WHO MAY BE AFFECTED BY THE PROJECT. CONTRACTOR'S DUTIES AND RESPONSIBILITIES FOR SAFETY IN CONNECTION WITH WORK SHALL CONTINUE UNTIL SUCH TIME AS ALL WORK IS COMPLETED, AND ENGINEER HAS ISSUED NOTICE TO CONTRACTOR THAT WORK IS COMPLETE.
- 20. HAZARDOUS MATERIALS, INCLUDING BUT NOT LIMITED TO OIL, GASOLINE, PAINT AND OTHER HAZARDOUS SUBSTANCES MUST BE PROPERLY STORED. BY THE CONTRACTOR. INCLUDING SECONDARY CONTAINMENTS. TO PREVENT SPILLS, LEAKS OR OTHER DISCHARGE, RESTRICTED ACCESS TO STORAGE AREAS MUST BE PROVIDED TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MCPA REGULATIONS. CONTRACTOR SHALL REMOVE SPILL OF FUELS. OILS. OR OTHER CHEMICALS IMMEDIATELY UPON DETECTION.

- 1. SEE GENERAL NOTES FOR ADDITIONAL PROJECT AND SITE INFORMATION.
- 2. CONTRACTOR SHALL CONFORM TO AND CONDUCT INSPECTIONS IN ACCORDANCE WITH THE SWPPP, NPDES PERMIT, AND CITY, STATE, AND WATERSHED DISTRICT PERMITS.
- 3. BEFORE SITE DISTURBANCE AND AS REQUIRED AS CONSTRUCTION PROGRESSES, CONTRACTOR SHALL INSTALL, MAINTAIN, REPAIR, AND REPLACE EROSION PREVENTION MEASURES AND SEDIMENT CONTROL DEVICES (INLET PROTECTION, CONSTRUCTION ENTRANCE, SILT FENCE, TEMPORARY EROSION PREVENTION BLANKET, ETC.) IN ACCORDANCE WITH THE SWPPP, NPDES PERMIT, AND CITY, STATE, AND WATERSHED DISTRICT PERMITS.
- 4. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED DEPENDING ON SITE CONDITIONS DURING CONSTRUCTION. COORDINATE WITH ENGINEER.
- 5. CONTRACTOR SHALL STABILIZE ALL EXPOSED SOIL AREAS WITHIN THE CONSTRUCTION LIMITS WITHIN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE THAT HAS TEMPORARILY (WILL NOT RESUME FOR A PERIOD EXCEEDING 7 CALENDAR DAYS) OR PERMANENTLY CEASED. STABILIZATION MUST BE INITIATED PROMPTLY.
- CONTRACTOR SHALL REMOVE ANY SEDIMENT THAT HAS TRACKED ONTO PAVED SURFACES BOTH ON AND OFFSITE WITHIN 24 HOURS AND AS DIRECTED BY CITY, OWNER, ENGINEER. SWEEP STREET IN ACCORDANCE WITH CITY, COUNTY. STATE AND NDPES PERMIT REQUIREMENTS.
- 7. CONTRACTOR SHALL PHASE GRADING WORK TO MINIMIZE THE DURATION THAT DISTURBED SOIL IS EXPOSED.
- 8. CONTRACTOR SHALL LOCATE SOIL STOCKPILES NO LESS THAN 50 FEET FROM ROADWAYS, STORMWATER INLETS, PONDS, WETLANDS, DRAINAGE CHANNELS, AND OTHER SURFACE WATERS. IF REMAINING FOR MORE THAN 7 DAYS, STABILIZE THE STOCKPILES BY MULCHING, VEGETATED COVER, TARPS, OR OTHER MEANS IN ACCORDANCE WITH THE NPDES PERMIT. PLACE PERIMETER SEDIMENT CONTROLS AROUND STOCKPILES TO CONTROL EROSION. COVER TEMPORARY STOCKPILES LOCATED ON PAVED SURFACES IF LEFT FROM MORE THAN 24 HOURS.
- 9. CONTRACTOR SHALL REMOVE ALL EROSION CONTROL MEASURES AFTER SITE HAS BEEN STABILIZED AND VEGETATION IS ESTABLISHED AS DIRECTED BY ENGINEER. EROSION CONTROL MEASURES USED FOR CONSTRUCTION MUST NOT BE REMOVED UNTIL AUTHORIZED BY OWNER OR ENGINEER.
- 10.STREAMBANK STABILIZATION PRACTICES SHALL CONSIST OF TWO LAYERS OF EROSION PREVENTION BLANKET. TEMPORARY EROSION PREVENTION BLANKET. CATEGORY 20 NATURAL FIBER NETTING WILL BE ON THE BOTTOM AGAINST THE GROUND. WITH TEMPORARY EROSION PREVENTION BLANKET CATEGORY 37 ROLANKA BIOD-MAT 40, OR APPROVED EQUIVALENT OVER THE TOP. BOTH BLANKETS WILL BE STAKED INTO THE GROUND TOGETHER WITH WOOD STAKES AS SPECIFIED.

11.MN STATE SEED MIXES USED ON THIS PROJECT INCLUDE:

- 11.1. 25-131 LOW MAINTENANCE TURF MIX SEEDED AT 220 LB/ACRE FOR ALL TURF GRASS RESTORATION AREAS.
- 11.2. 34-261 RIPARIAN SOUTH & WEST MIX SEEDED AT 31.5 LB/ACRE FOR ALL STABILIZED STREAMBANK AREAS.
- 11.2. 36-711 WOODLAND EDGE CENTRAL MIX SEEDED AT 35.5 LB/ACRE FOR ALL BUCKTHORN REMOVAL AREAS.

GRADING NOTES

- 1. SEE GENERAL NOTES FOR ADDITIONAL PROJECT AND SITE INFORMATION.
- 2. PROPOSED CONTOURS ARE TO FINISHED SURFACE GRADE, UNLESS NOTED OTHERWISE.
- 3. THE SITE HAS NOT BEEN DESIGNED TO BALANCE THE ON-SITE MATERIALS. ADDITIONAL ONSITE EXCAVATION AND EXPORT OF SOIL WILL BE NECESSARY TO ACHIEVE FLOODPLAIN FILL COMPENSATORY STORAGE VOLUME. EXCESS MATERIAL, UNLESS NOTED OTHERWISE, IS THE PROPERTY OF THE CONTRACTOR AND IS TO BE MOVED AND DISPOSED OF OFFSITE IN ACCORDANCE WITH APPLICABLE LAWS.
- 4. CONTRACTOR SHALL EXCAVATE AND DISPOSE OF UNSUITABLE OR CONTAMINATED SOILS DISCOVERED ONSITE IN ACCORDANCE WITH APPLICABLE REGULATIONS. THERE IS ONE KNOWN AREA OF CONTAMINATED SOIL.
- 5. ALL DISTURBED PERVIOUS AREAS ARE TO RECEIVE 4 INCHES OF IMPORTED TOPSOIL, UNLESS NOTED OTHERWISE

DEWATERING NOTES

- AND NPDES PERMIT

TREE PRESERVATION NOTES

- PREVENT DRYING.
- INCIDENTAL

HORIZONTAL AND VERTICAL CONTROL NOTES

EROSION CONTROL NOTES

1. CONTRACTOR SHALL ANTICIPATE BASE FLOW AND STOMRWATER RUNOFF IN THE CREEK CHANNEL. NO BID ITEM HAS BEEN PROVIDED FOR DEWATERING AS ALL DEWATERING WORK NECESSARY FOR CONSTRUCTION WILL BE CONSIDERED INCIDENTAL TO OTHER WORK.

2. CONTRACTOR SHALL OBTAIN APPLICABLE REQUIRED PERMITS (INCLUDING MN DNR WATER APPROPRIATION PERMIT) AND SUBMIT DEWATERING PLAN TO ENGINEER FOR REVIEW. DEWATERING MUST MEET PERMIT REQUIREMENTS AND BE ACCEPTED BEFORE STARTING CONSTRUCTION ACTIVITIES.

3. CONTRACTOR MUST DEWATER IN ACCORDANCE WITH THE PROJECT SWPPP

4. CONTRACTOR MUST DISCHARGE TURBID OR SEDIMENT-LADEN WATER RELATED TO DEWATERING OR BASIN DRAINING (E.G. PUMPED DISCHARGES, TRENCH/DITCH CUTS FOR DRAINAGE) TO A TEMPORARY OR PERMANENT SEDIMENTATION BASIN ON THE PROJECT SITE UNLESS INFEASIBLE. CONTRACTOR MAY DISCHARGE FROM THE TEMPORARY OR PERMANENT SEDIMENTATION BASINS TO THE SURFACE WATERS IF THE BASIN WATER HAS BEEN VISUALLY CHECKED TO ENSURE ADEQUATE TREATMENT HAS BEEN OBTAINED IN THE BASIN AND THAT NUISANCE CONDITIONS (SEE MINNESOTA RULES CHAPTER 7050.0210, SUBPART 2) WILL NOT RESULT FROM THE DISCHARGE. IF THE WATER CANNOT BE DISCHARGED TO A SEDIMENTATION BASIN PRIOR TO ENTERING THE SURFACE WATER. IT MUST BE TREATED WITH THE APPROPRIATE BMPs (E.G. SILT BAGS), SUCH THAT THE DISCHARGE DOES NOT ADVERSELY AFFECT THE RECEIVING WATER OR DOWNSTREAM PROPERTIES. IF THE CONTRACTOR MUST DISCHARGE WATER THAT CONTAINS OIL OR GREASE, THE CONTRACTOR MUST USE AN OIL-WATER SEPARATOR OR SUITABLE FILTRATION DEVICE (E.G. CARTRIDGE FILTERS, ABSORBENTS PADS) PRIOR TO DISCHARGING THE WATER. THE CONTRACTOR MUST ENSURE THAT DISCHARGE POINTS ARE ADEQUATELY PROTECTED FROM EROSION AND SCOUR. THE DISCHARGE MUST BE DISPERSED OVER NATURAL ROCK RIPRAP. SANDBAGS, PLASTIC SHEETING, OR OTHER ACCEPTED ENERGY DISSIPATION MEASURES.

5. CONTRACTOR MUST DISCHARGE WATER FROM DEWATERING OR BASIN-DRAINING ACTIVITIES IN A MANNER THAT DOES NOT CAUSE NUISANCE CONDITIONS, EROSION IN RECEIVING CHANNELS OR ON DOWN SLOPE PROPERTIES, OR INUNDATION IN WETLANDS CAUSING SIGNIFICANT ADVERSE IMPACT TO THE WETLAND.

6. IF THE CONTRACTOR IS USING FILTERS WITH BACKWASH WATER. THE CONTRACTOR MUST HAUL THE BACKWASH WATER AWAY FOR DISPOSAL RETURN THE BACKWASH WATER TO THE BEGINNING OF THE TREATMENT PROCESS, OR INCORPORATE THE BACKWASH WATER INTO THE SITE IN A MANNER THAT DOES NOT CAUSE EROSION OR POLLUTION. THE CONTRACTOR MUST REPLACE AND CLEAN THE FILTER MEDIA USED IN DEWATERING DEVICES WHEN REQUIRED TO RETAIN ADEQUATE FUNCTION.

1. CONTRACTOR SHALL PROTECT EXISTING TREES THAT ARE NOT TO BE REMOVED. DO NOT PERFORM ACTIONS WITHIN THE DRIP LINE AREA THAT MAY HARM THE TREE AND COMPACT THE SOIL, INCLUDING EXCAVATION, STORING MATERIALS, PARKING AND TRAFFIC DURING CONSTRUCTION. WHERE CONSTRUCTION REQUIRES DISTURBANCE WITHIN THE PROTECTED AREAS. DISTURB THE ROOT ZONE AS LITTLE AS POSSIBLE.

2. WHEN TREE ROOTS OVER 1" ARE ENCOUNTERED THAT MUST BE REMOVED. CONTRACTOR SHALL CUT ROOTS CLEANLY AS FAR FROM THE TREE AS POSSIBLE AND IMMEDIATELY WATER AND BACKFILL OVER THE ROOTS TO

3. PROTECTION OF TREES NOT DESIGNATED FOR REMOVAL SHALL BE

1. THE HORIZONTAL COORDINATE SYSTEM FOR THIS PLAN IS NAD83 (2011) HENNEPIN COUNTY COORDINATES US SURVEY FEET. 2. THE VERTICAL DATUM FOR THIS PLAN IS NAVD 88



P.O. BOX 448 VICTORIA, MN 55386 PHONE: (952) 261-9990 WWW.MIDWESTWETLANDS.CO

CERTIFICATION:

HEREBY CERTIFY THAT THIS PLAN SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA

LUCIUS JONETT

LICENSE NO.: 52856 DATE: 10-31-2024

DATE:	DESCRIPTION:	ISSUE NO.:
09/09/2024	60% PLAN SET	01
10/30/2024	90% PLAN SET	02

AM Ш Ŕ \mathbf{O} \vdash Ш S S \mathbf{C} \bigcap 0 Ζ 0M RA S Ο OL Ľ Ш **(**) ND ND ND Ο Ũ CLIENT: City of Plymouth 3400 PLYMOUTH BLVD PLYMOUTH, MN 55447 PHONE: 763-509-5000 WWW.PLYMOUTHMN.COM PROJECT NO.: 0017-03 DWN BY: CHK'D BY: APP'D BY: LNJ LNJ LNJ 10/30/2024 ISSUE DATE: ISSUE NO .: SHEET TITLE:

CONSTRUCTION NOTES

G-102

SHEET NO .:

PROJECT INFORMATION

PROJECT NAME: PONDEROSA WOODS STREAM RESTORATION PROJECT LOCATION: 1830 IVES LANE NORTH, PLYMOUTH, MN 55441 PROJECT TYPE: STREAM BANK RESTORATION

TOTAL AREA DISTURBED BY CONSTRUCTION: ±4.3 ACRES. TOTAL SITE AREA: ±5.8 ACRES. ESTIMATED CONSTRUCTION DATES: WINTER 2024 - SUMMER 2025

CUMULATIVE IMPERVIOUS SURFACE/PERMANENT STORMWATER MANAGEMENT REQUIREMENTS: THERE IS CURRENTLY ±0.0 ACRES OF EXISTING IMPERVIOUS SURFACE IN THE PROJECT AREA.

THE PROPOSED AREA OF IMPERVIOUS IS ±0.0 ACRES RESULTING IN A ±0.0 ACRE NET INCREASE IN IMPERVIOUS SURFACE.

THE SITE ULTIMATELY DRAINS TO PLYMOUTH CREEK AND THEN MEDICINE LAKE, BOTH OF WHICH ARE LISTED AS AN IMPAIRED WATER FOR AQUATIC LIFE AND AQUATIC RECREATION. THERE ARE NO CURRENT EPA APPROVED TMDLS FOR THESE WATERBODIES.

THE CONSTRUCTION PLANS OUTLINE STREAMBANK STABILIZATION PRACTICES INCLUDING BUCKTHORN REMOVAL, TREE REMOVAL, RIPRAP, RIPRAP TOE, CROSS VANES, SEEDING, HYDROMULCHING AND INSTALLATION OF EROSION CONTROL BLANKET FOR VEGETATIVE RE-ESTABLISHMENT

PARTY RESPONSIBLE FOR LONG TERM OPERATION AND MAINTENANCE OF THE SITE (OWNER)

CITY OF PLYMOUTH CONTACT: BEN SCHARENBROICH, WATER RESOURCES SUPERVISOR

CONTACT PHONE: (763) 509-5527

CONTACT EMAIL: BSCHARENBROICH@PLYMOUTHMN.GOV

PARTY RESPONSIBLE FOR IMPLEMENTATION OF THE SWPPP (CONTRACTOR):

TBD - CONTRACTOR SHALL PROVIDE A CHAIN OF RESPONSIBILITY WITH ALL OPERATORS ON THE SITE FOR INCORPORATION INTO THIS SWPPP DOCUMENT TO ENSURE THAT THE SWPPP WILL BE IMPLEMENTED AND STAY IN EFFECT UNTIL THE CONSTRUCTION PROJECT IS COMPLETE (THROUGH FINAL STABILIZATION AND NOT SUBMITTAL). CONTRACTOR SHALL ALSO PROVIDE DOCUMENTATION OF PERSONNEL TRAINING IN ACCORDANCE WITH THE PERMIT FOR INCORPORATION INTO THIS SWPPP DOCUMENT AS SOON AS THE PERSONNEL FOR THE PROJECT HAVE BEEN DETERMINED. CONTRACTOR IS RESPONSIBLE FOR KEEPING A FINAL SWPPP DOCUMENT, CONTAINING THE INFORMATION REQUIRED ABOVE, AT THE CONSTRUCTION SITE FOR THE DURATION OF THE PROJECT.

SWPPP DOCUMENTS

THE SWPPP IS COMPOSED OF, BUT NOT LIMITED TO, THE BELOW PROJECT DOCUMENTS. THESE DOCUMENTS SHALL BE KEPT ON THE PROJECT SITE AT ALL TIMES THROUGHOUT CONSTRUCTION. THE SWPPP SHALL BE AMENDED BY THE PERSON RESPONSIBLE TO INCLUDE ANY DOCUMENTS NECESSARY TO ENSURE ADHERENCE TO THE GENERAL PERMIT.

PONDEROSA WOODS STREAM RESTORATION CONSTRUCTION DRAWINGS BY MIDWEST WETLAND IMPROVEMENTS DATED OCTOBER 31, 2024

RECORD RETENTION - THE SWPPP, ALL CHANGES TO IT, AND INSPECTION AND MAINTENANCE RECORDS MUST BE KEPT ON-SITE DURING CONSTRUCTION; THE CONSTRUCTION DRAWINGS ARE INCORPORATED HEREIN BY REFERENCE, AND A COPY OF THE PLAN SET SHOULD BE KEPT ON-SITE WITH THE SWPPP RECORDS. THE OWNER MUST RETAIN A COPY OF THE SWPPP ALONG WITH THE FOLLOWING RECORDS FOR THREE (3) YEARS AFTER SUBMITTAL OF THE NOTICE OF TERMINATION:

- 1. ANY OTHER PERMITS REQUIRED FOR THE PROJECT;
- RECORDS OF ALL INSPECTION AND MAINTENANCE CONDUCTED DURING CONSTRUCTION;
- 3 ALL PERMANENT OPERATIONS AND MAINTENANCE AGREEMENTS THAT HAVE BEEN IMPLEMENTED, INCLUDING ALL RIGHT OF WAY,
- CONTRACT, COVENANTS AND OTHER BINDING REQUIREMENTS REGARDING PERPETUAL MAINTENANCE; AND
- 4. ALL REQUIRED CALCULATIONS FOR DESIGN OF THE TEMPORARY AND PERMANENT STORMWATER MANAGEMENT SYSTEMS



SOIL MAP

EROSION AND SEDIMENT CONTROL

PRIOR TO ANY SITE DISTURBANCE, AND AS REQUIRED AS CONSTRUCTION PROGRESSES, ANY PERMIT REQUIRED EROSION PREVENTION MEASURES AND THE SEDIMENT CONTROL DEVICES (WOOD MULCH CONSTRUCTION ENTRANCE, BIOLOG, SILT FENCE, EROSION CONTROL BLANKET) SHOWN ON THE CONSTRUCTION DRAWINGS WILL BE INSTALLED AT THE SITE.

ALL EXPOSED SOIL AREAS WITHIN THE CONSTRUCTION LIMITS WILL BE STABILIZED WITHIN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY (WILL NOT RESUME FOR A PERIOD EXCEEDING 7 CALENDAR DAYS) OR PERMANENTLY CEASED. STABILIZATION WILL BE INITIATED IMMEDIATELY. EXPOSED SOIL AREAS MUST HAVE TEMPORARY EROSION PROTECTION (SLASH MULCH, EROSION CONTROL BLANKET, SEED) OR PERMANENT COVER YEAR ROUND.

CONTRACTOR SHALL IMPLEMENT APPROPRIATE CONSTRUCTION PHASING, VEGETATIVE BUFFER STRIPS, HORIZONTAL SLOPE GRADING, AND OTHER CONSTRUCTION PRACTICES THAT MINIMIZE EROSION WHEN PRACTICAL. THE NORMAL WETTED PERIMETER OF ANY TEMPORARY OR PERMANENT DRAINAGE DITCH THAT DRAINS WATER FROM A CONSTRUCTION SITE, OR DIVERTS WATER AROUND A SITE, MUST BE STABILIZED WITHIN 200 LINEAL FEET FROM THE PROPERTY EDGE, OR FROM THE POINT OF DISCHARGE TO ANY SURFACE WATER. STABILIZATION MUST BE COMPLETED WITHIN 24 HOURS OF CONNECTING TO A SURFACE WATER. PIPE OUTLETS MUST BE PROVIDED WITH TEMPORARY OR PERMANENT ENERGY DISSIPATION WITHIN 24 HOURS OF CONNECTION TO A SURFACE WATER.

SWPPP IMPLEMENTATION, PHASING, AND SEQUENCE OF CONSTRUCTION

BMP AND EROSION CONTROL INSTALLATION SEQUENCE SHALL BE AS FOLLOWS: 1. INSTALL WOOD MULCH CONSTRUCTION ENTRANCE AND

- PERIMETER CONTROL.
- 2. PREPARE TEMPORARY STORAGE, PARKING, AND PHASING AREAS. 3. PERFORM BUCKTHORN REMOVAL IN THE DESIGNATED PROJECT
- AREA. 4. PERFORM CLEARING AND GRUBBING OF THE SITE.
- 6. PERFORM MASS GRADING, ROUGH GRADE TO ESTABLISH PROPOSED DRAINAGE PATTERNS
- START CONSTRUCTION OF STREAM BANK AND TRIBUTARY CHANNEL STABILIZATION PRACTICES.
- TEMPORARILY SEED WITH PURE LIVE SEED THROUGHOUT CONSTRUCTION DISTURBED AREAS THAT WILL BE INACTIVE FOR SEVEN (7 DAYS) OR MORE AS REQUIRED BY NPDES PERMIT.

SEDIMENT CONTROL PRACTICES MUST MINIMIZE SEDIMENT FROM ENTERING SURFACE WATERS, INCLUDING CURB AND GUTTER SYSTEMS AND STORM SEWER INLETS. THE FOLLOWING MEASURES WILL BE TAKEN AS SEDIMENT CONTROL PRACTICES IN ORDER TO MINIMIZE SEDIMENTS FROM ENTERING SURFACE WATERS:

- 1. INSTALLATION OF SEDIMENT CONTROL PRACTICES ON ALL DOWN
- GRADIENT PERIMETERS PRIOR TO LAND DISTURBING ACTIVITIES. STREET SWEEPING SHALL BE PERFORMED IF VEHICLE TRACKING BMPS ARE NOT ADEQUATE TO PREVENT SEDIMENT TRACKING. TRACKED SEDIMENT MUST BE REMOVED FROM ALL PAVED SURFACES BOTH ON AND OFFSITE WITHIN 24 HOURS OF DISCOVERY PER THE PERMIT.

THE FOLLOWING GUIDELINES WILL BE USED TO DETERMINE IF POLLUTION CONTROL DEVICES REQUIRE MAINTENANCE. REPAIR. OR **REPLACEMENT:**

-IF SEDIMENT CONTROL DEVICES SUCH AS SILT FENCE ARE FILLED TO 1/3 THE HEIGHT OF THE FENCE. REMOVE ALL SEDIMENT WITHIN 24 HOURS OF DETECTION OR NOTIFICATION.

-IF INLET PROTECTION DEVICES APPEAR PLUGGED WITH SEDIMENT. ARE FILLED TO 1/3 CAPACITY, OR HAVE STANDING WATER AROUND THEM, REMOVE THE SEDIMENT AND CLEAN OR REPLACE THE FILTER WITHIN 24 HOURS OF DETECTION OR NOTIFICATION.

-IF THE WOOD MULCH CONSTRUCTION ENTRANCE(S) ARE FILLED WITH SEDIMENT EITHER REPLACE THE ENTRANCE OR ADD ADDITIONAL GRAVEL WITH 24 HOURS OF DETECTION OR NOTIFICATION.

-IF SEDIMENT FROM THE SITE IS OBSERVED ON ADJACENT STREETS OR OTHER PROPERTIES, THE INSPECTOR SHALL IDENTIFY THE SOURCE AND DISCHARGE LOCATION OF THE SEDIMENT AND INSTRUCT

TO IMPLEMENT ADDITIONAL EROSION AND SEDIMENT CONTROLS AT THOSE LOCATIONS TO PREVENT FUTURE DISCHARGES. -IF BUILDING MATERIALS, CHEMICALS, OR GENERAL REFUSE IS BEING

USED, STORED, DISPOSED OF, OR OTHERWISE MANAGED INAPPROPRIATELY, CORRECT SUCH DEFECTS WITHIN 24 HOURS OF DETECTION OR NOTIFICATION.

-IF EXCESSIVE SEDIMENTS OR DEBRIS ARE OBSERVED AT THE FLARED END SECTION OUTFALLS, THE INSPECTOR SHALL DETERMINE THE SOURCE AND DISCHARGE LOCATIONS OF SUCH MATERIALS. IF THE DISCHARGE HAS OCCURRED ON THE PROPERTY, REMOVE THE SEDIMENTS AND DEBRIS WITHIN 24 HOURS OF NOTIFICATION AND CORRECT THE SOURCE OF SUCH MATERIALS AS DIRECTED BY THE INSPECTOR

POLLUTION PREVENTION MEASURES

SOLID WASTE

SOLID WASTE, INCLUDING BUT NOT LIMITED TO, COLLECTED ASPHALT AND CONCRETE MILLINGS, FLOATING DEBRIS, PAPER, PLASTIC, FABRIC, CONSTRUCTION AND DEMOLITION DEBRIS AND OTHER WASTE MUST BE DISPOSED OF PROPERLY AND MUST COMPLY WITH MPCA DISPOSAL REQUIREMENTS.

HAZARDOUS MATERIALS

HAZARDOUS MATERIALS, INCLUDING BUT NOT LIMITED TO OIL GASOLINE, PAINT AND ANY HAZARDOUS SUBSTANCE MUST BE PROPERLY STORED INCLUDING SECONDARY CONTAINMENTS, TO PREVENT SPILLS, LEAKS OR OTHER DISCHARGE. RESTRICTED ACCESS TO STORAGE AREAS MUST BE PROVIDED TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MCPA REGULATIONS.

CONSTRUCTION EQUIPMENT/VEHICLES

EXTERNAL WASHING OF TRUCKS AND OTHER CONSTRUCTION VEHICLES MUST BE LIMITED TO A DEFINED AREA OF THE SITE. RUNOFF MUST BE CONTAINED AND WASTE PROPERLY DISPOSED OF. NO ENGINE DEGREASING IS ALLOWED ON SITE. REASONABLE STEPS TO PREVENT THE DISCHARGE OF SPILLED OR LEAKED CHEMICALS SHALL BE TAKEN. ADEQUATE SUPPLIES MUST BE AVAILABLE AT ALL TIMES TO CLEAN UP DISCHARGED MATERIALS; CONDUCT FUELING IN A CONTAINED AREA UNLESS INFEASIBLE.

FERTILIZERS AND LANDSCAPE MATERIALS MUST BE UNDER COVER TO PREVENT THE DISCHARGE OF POLLUTANTS OR PROTECTED BY SIMILARLY EFFECTIVE MEANS DESIGNED TO MINIMIZE CONTACT WITH STORMWATER.

PORTABLE TOILETS MUST BE POSITIONED SO THAT THEY ARE SECURE AND WILL NOT BE TIPPED OR KNOCKED OVER - SANITARY WASTE MUST BE DISPOSED OF PROPERLY.

GENERAL SWPPP NOTES

DEWATERING IS NOT ANTICIPATED TO BE REQUIRED. IN THE EVENT THAT DEWATERING IS NECESSARY CONTRACTOR SHALL COMPLY WITH PERMIT PART IV.D. REQUIREMENTS FOR DEWATERING.

THIS SWPPP SHALL BE AMENDED BY THE CONTRACTOR IN ACCORDANCE WITH THE PERMIT AS NECESSARY TO INCLUDE ADDITIONAL REQUIREMENTS TO CORRECT PROBLEMS IDENTIFIED OR ADDRESS SITUATIONS PER PART III.B. OF THE PERMIT.

FINAL STABILIZATION

ALL PERVIOUS AREAS DISTURBED BY CONSTRUCTION AS DESIGNATED WILL RECEIVE VEGETATIVE COVER ACCORDING TO THE PLANS AND SPECIFICATIONS AND WITHIN THE SPECIFIED VEGETATIVE TIME SCHEDULE. FINAL STABILIZATION WILL OCCUR WHEN THE SITE HAS A UNIFORM VEGETATIVE COVER WITH A DENSITY OF 70% OVER THE RESTORED PERVIOUS AREAS. ALL TEMPORARY SYNTHETIC EROSION PREVENTION AND SEDIMENT CONTROL BMPS (SUCH AS SILT FENCE) MUST BE REMOVED AS PART OF THE SITE FINAL STABILIZATION. ALL SEDIMENT MUST BE CLEANED OUT OF CONVEYANCES AND TEMPORARY SEDIMENTATION BASINS IF APPLICABLE. NOTICE OF TERMINATION (NOT) MUST BE SUBMITTED WITHIN 30 DAYS OF FINAL STABILIZATION.

IMPAIRED WATERS, SPECIAL WATERS, AND WEILAND

THIS PROJECT IS LOCATED WITHIN ONE MILE OF. AND ULTIMATELY DISCHARGES TO, AN IMPAIRED WATER, PLYMOUTH CREEK AND MEDICINE LAKE ARE LOCATED WITHIN THE PROJECT LOCATION AND BOTH ARE LISTED AS IMPAIRED FOR AQUATIC LIFE AND AQUATIC RECREATION. DISCHARGE TO AN IMPAIRED WATER REQUIRES IMPLEMENTATION OF PARTS C.1 AND C.2 OF APPENDIX A OF THE PERMIT AS INCORPORATED INTO THIS SWPPP DOCUMENT.

THE PROJECT WILL TEMPORARILY IMPACT WETLANDS FOR CONSTRUCTION ACCESS.

SITE SOILS - SITE SOILS ARE SHOWN ON THIS SHEET. THIS PROJECT IS NOT LOCATED IN A KARST AREA.

2706910

2706160

Public Watercourses
Public Water Watercourse
Public Ditch/Altered Natural Watercourse
Public Waters Basins
NWI Cowardin
Class
Aquatic Bed/

INSPECTIONS

Nonpersistent Emergent

THE INSPECTION LOG WILL BE COMPLETED BY THE CONTRACTOR FOR THE CONSTRUCTION SITE. INSPECTOR(S): TBD - TRAINING DOCUMENTATION (PER PART IV.E OF THE PERMIT) WILL BE INCORPORATED INTO THIS SWPPP AS SOON AS THE PERSONNEL FOR THE PROJECT HAVE BEEN DETERMINED. THE CONTRACTOR WILL MAKE CORRECTIONS OR REPAIRS REQUIRED TO COMPLY WITH THE PERMIT.

PROJECT.


-RECORD DATE AND TIME OF INSPECTION. DEBRIS.

THE GC MUST UPDATE THE SWPPP, INCLUDING THE JOBSITE BINDER AND SITE MAPS, TO REFLECT THE PROGRESS OF CONSTRUCTION ACTIVITIES AND GENERAL CHANGES TO THE PROJECT SITE. UPDATES SHALL BE MADE DAILY TO TRACK PROGRESS WHEN ANY OF THE FOLLOWING ACTIVITIES OCCUR: BMP INSTALLATION, MODIFICATION OR REMOVAL, CONSTRUCTION ACTIVITIES (E.G. PAVING, SEWER INSTALLATION, ETC), CLEARING, GRUBBING, GRADING, OR TEMPORARY AND PERMANENT STABILIZATION.

THE CONTRACTOR MAY UPDATE OR MODIFY THE SWPPP WITHOUT ENGINEER APPROVAL IN AN EMERGENCY SITUATION TO PREVENT SEDIMENT DISCHARGE OR PROTECT WATER QUALITY. THE CONTRACTOR IS ULTIMATELY RESPONSIBLE TO ENSURE COMPLIANCE WITH THE PERMIT AND PROTECTION OF DOWNSTREAM WATER QUALITY.

CERTIFICATION

IN ACCORDANCE WITH PART III.A.2.A.I. OF THE GENERAL PERMIT AUTHORIZATION TO DISCHARGE STORMWATER ASSOCIATED WITH CONSTRUCTION ACTIVITY UNDER THE NPDES. THE PREPARER OF THIS DOCUMENT WAS TRAINED UNDER THE UNIVERSITY OF MINNESOTA EROSION AND SEDIMENT CONTROL CERTIFICATION PROGRAM. LUCIUS JONETT'S CERTIFICATION IN DESIGN OF SWPPP IS VALID THROUGH MAY 31, 2025.




INSPECTIONS AT THE SITE WILL BE COMPLETED IN ACCORDANCE WITH THE PERMIT AS FOLLOWS: ONCE EVERY SEVEN (7) DAYS DURING ACTIVE CONSTRUCTION AND, WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS.

1. THE INDIVIDUAL PERFORMING INSPECTIONS MUST BE TRAINED AS REQUIRED BY PART IV.E OF THE PERMIT. TRAINING DOCUMENTATION SHALL BE PROVIDED BY THE CONTRACTOR FOR INCORPORATION INTO THE SWPPP. INSPECTIONS MUST INCLUDE STABILIZED AREAS, EROSION PREVENTION AND SEDIMENT CONTROL BMPS, AND INFILTRATION AREAS. CORRECTIVE ACTIONS MUST BE IDENTIFIED AND DATE OF CORRECTION MUST BE NOTED AS IDENTIFIED IN SECTION IV.E. OF THE PERMIT. ANY OFFSITE DISCHARGE MUST BE DOCUMENTED AS IDENTIFIED IN SECTION IV.E.2.F OF THE PERMIT. ANY AMENDMENTS TO THE SWPPP PROPOSED AS A RESULT OF THE INSPECTION MUST BE DOCUMENTED WITHIN SEVEN (7) CALENDAR DAYS. AN INSPECTION LOG IS ALSO ATTACHED; THE INSPECTION LOG AND SWPPP MUST BE KEPT ON-SITE FOR THE DURATION OF THE CONSTRUCTION

AT A MINIMUM, THE FOLLOWING SHALL BE COMPLETED DURING EACH INSPECTION:

- -RECORD RAINFALL RECORDS SINCE THE MOST RECENT INSPECTION.
- -INSPECT THE SITE FOR EXCESS EROSION AND SEDIMENTATION.
- -INSPECT THE SITE FOR DEBRIS, TRASH, AND SPILLS.
- -INSPECT TEMPORARY EROSION AND SEDIMENTATION CONTROL DEVICES.
- -INSPECT CONSTRUCTION ENTRANCES FOR SEDIMENT TRACKING ONTO PUBLIC STREETS. -RECORD RECOMMENDED REPAIRS AND MODIFICATIONS TO EROSION AND SEDIMENT CONTROLS.
- -RECOMMEND ANY NECESSARY CHANGES TO THIS SWPPP. -RECORD REPAIRS AND MODIFICATIONS IMPLEMENTED SINCE PREVIOUS INSPECTIONS.
- -INSPECT THE ADJACENT STREETS AND CURB AND GUTTER FOR SEDIMENT, LITTER, AND CONSTRUCTION





CONSTRUCTION STAGING AREA. CONTRACTOR TO PROTECT EXISTING FACILITIES.

CONTRACTOR TO PROVIDE WARNING SIGNS AND TRAFFIC CONTROL WHILE CROSSING WEST

MIDWEST improvements

P.O. BOX 448 VICTORIA, MN 55386 PHONE: (952) 261-9990 WWW.MIDWESTWETLANDS.COM


CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN, PREPARED VERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

UCIUS JONE LICENSE NO.: 52856


10-31-2024 DATE

	DAT	E: _		10-3	1-20	24		-
	ISSUE NO.:	01	02					
	E: DESCRIPTION:		10/30/2024 90% PLAN SET					
/	DATE:	09/09/2024	10/30/2					



LEGEND

	901		
	900		
	- WET-		
		<u>`</u>	
>-		->	
	\otimes		
	S		
	S		
>> -		->>	
	\triangleleft		
	\odot		



EXISTING EASEMENT LINE EXISTING DRAINAGE AND UTILITY EASEMENT LINE EXISTING PARCEL LINE EXISTING MINOR CONTOUR – EXISTING MAJOR CONTOUR EXISTING WETLAND BOUNDARY EXISTING WATER EDGE OF STREAM EXISTING SANITARY SEWER EXISTING CURB STOP EXISTING SANITARY MANHOLE EXISTING STORM SEWER MANHOLE EXISTING STORM SEWER EXISTING STORM SEWER INLET EXISTING FLARED END SECTION EXISTING TREE

STREAM CONSTRUCTION LIMITS EDGE OF CREEK (TOE OF BANK) CENTER LINE LOW FLOW 100 YEAR FLOOD ELEVATION (893.64 NAVD 88) REMOVE TREE

BUCKTHORN REMOVAL AND TREATMENT AREA

AM STRE, C **PROJE**(DS MOO TION ONDEROSA RESTORAT

JEC⁻ PRO,

 \overline{O}

PROJECT NO .:

ISSUE DATE:

SHEET TITLE:

SHEET NO .:

ISSUE NO .:

CLIENT:

Õ

Plymouth	
----------	--

3400 PLYMOUTH BLVD

PLYMOUTH, MN 55447 PHONE: 763-509-5000

WWW.PLYMOUTHMN.COM

DWN BY: CHK'D BY: APP'D BY: LNJ LNJ LNJ LNJ

SITE ACCESS AND


BUCKTHORN


TREATMENT

C-101

0017-03


10/30/2024





	901	
	- 900	
	WET	
>		->
	\otimes	
	S	
	S	
>>		->>
	\triangleleft	
	\odot	
	·	
	\bigotimes	~~~







CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

	Ċ	Ju	úu	3)	Jence	tt		
UC	IUS	JOI	NET.	Г				
CE	ENS	E NO	D.: _		52	856		
AT	E:_			10-3	1-20	24		

6 8

AM

STRE,

SO

MOO

PONDEROSA RESTORAT

CLIENT:

PROJECT NO .:

ISSUE DATE:

SHEET TITLE:

SHEET NO .:

ISSUE NO .:

Plymouth

3400 PLYMOUTH BLVD PLYMOUTH, MN 55447 PHONE: 763-509-5000

WWW.PLYMOUTHMN.COM

DWN BY: CHK'D BY: APP'D BY: LNJ LNJ LNJ LNJ

TREE REMOVALS 2

C-103

0017-03

10/30/2024

C

ROJE

Ω

 \leq

#

JECT

PRO,

 \overline{O}

TION


TRAFFIC CONTROL WHILE CROSSING WEST MEDICINE LAKE DRIVE. ROAD CLOSURES ARE NOT ALLOWED.

CONSTRUCTION STAGING AREA.

CONTRACTOR TO PROTECT

EXISTING FACILITIES.

LEGEND



EXISTING DRAINAGE AND UTILITY EASEMENT LINE EXISTING MINOR CONTOUR EXISTING WETLAND BOUNDARY EXISTING WATER EDGE OF STREAM EXISTING SANITARY SEWER EXISTING CURB STOP EXISTING SANITARY MANHOLE EXISTING STORM SEWER MANHOLE EXISTING STORM SEWER EXISTING STORM SEWER INLET EXISTING FLARED END SECTION EXISTING TREE

STREAM CONSTRUCTION LIMITS ------ SITE ACCESS ROUTE TOP OF BANK

EDGE OF CREEK (TOE OF BANK) CENTER LINE LOW FLOW 100 YEAR FLOOD ELEVATION

(893.64 NAVD 88) REMOVE TREE

BUCKTHORN REMOVAL AND TREATMENT AREA

Tree		Deciduos DBH	Conifer Height	Observed Health		Tree	Deciduos DBH	Conifer Height	Observed Health
ID #	Tree Species	(Inches)	(Feet)	Condition	Comments	ID # Tree Species	(Inches)	(Feet)	Condition
	Willow/Black	7	()	Healthy		165 Box Elder	10	(,	Healthy
1	Birch/River	10		Healthy		166 Box Elder	7		Healthy
2	Birch/River	8		Healthy		167 Maple/Sugar	20		Healthy
	Birch/Paper	5		Healthy	multi-stem 6 at 4in	170 Maple/Sugar	6		Healthy
	Birch/River	11		Healthy		171 Maple/Sugar	20		Healthy
	Box Elder	14		Healthy		172 Maple/Sugar	11		Healthy
	Box Elder	11		Healthy		174 Maple/Sugar	6		Healthy
	Cottonwood	13		Healthy		176 Maple/Sugar	6		Healthy
	Cottonwood Cottonwood	27 15		Healthy Healthy		179 Maple/Sugar 180 Maple/Sugar	10 9		Healthy Healthy
	Box Elder	8		Healthy		181 Maple/Sugar	27		Healthy
	Cottonwood	28		Healthy		182 Maple/Sugar	5		Healthy
	Box Elder	15		Healthy		183 Maple/Sugar	23		Healthy
	Box Elder	6		Healthy		184 Maple/Sugar	6		Healthy
22	Box Elder	15		Healthy		185 Maple/Sugar	18		Healthy
23	Box Elder	6		Healthy		186 Maple/Sugar	6		Healthy
26	Box Elder	14		Healthy		187 Maple/Sugar	18		Healthy
	Box Elder	13		Healthy		188 Maple/Sugar	6		Healthy
	Cottonwood	15		Healthy		189 Maple/Sugar	8		Healthy
	Box Elder	15		Healthy		191 Elm/American	8		Healthy
	Cottonwood	34		Healthy		192 Elm/American	10		Healthy
	Cottonwood	33 8		Healthy		201 Elm/American 202 Elm/American	9 14		Healthy
	Box Elder Cottonwood	o 35		Healthy Healthy		202 Eini/American 203 Cottonwood	33		Healthy Healthy
	Cottonwood	31		Healthy		204 Elm/American	6		Healthy
	Box Elder	8		Healthy		205 Cottonwood	29		Healthy
	Box Elder	6		Healthy		206 Cottonwood	32		Healthy
	Elm/American	7		Healthy		207 Cottonwood	28		Healthy
66	Box Elder	8		Healthy		212 Box Elder	16		Healthy
68	Elm/American	14		Healthy		217 Box Elder	8		Healthy
69	Maple/Sugar	8		Healthy		218 Box Elder	18		Healthy
	Box Elder	16		Healthy		219 Box Elder	16		Healthy
	Maple/Sugar	6		Healthy		220 Box Elder	12		Healthy
	Maple/Sugar	8		Healthy		221 Box Elder	18		Healthy
	Box Elder	15		Healthy		222 Elm/American 223 Elm/American	15 9		Healthy
	Maple/Sugar	9 16		Healthy		223 Eini/American 224 Box Elder	9 20		Healthy Healthy
	Maple/Sugar Elm/American	18		Healthy Healthy		224 Box Elder	16		Healthy
	Elm/American	8		Healthy		228 Box Elder	23		Healthy
	Elm/American	6		Healthy		230 Box Elder	8		Healthy
	Elm/American	7		Healthy		231 Box Elder	12		Healthy
87	Maple/Sugar	6		Healthy		232 Box Elder	16		Healthy
89	Box Elder	8		Healthy		233 Box Elder	8		Healthy
92	Elm/American	18		Healthy		236 Box Elder	11		Healthy
	Elm/American	9		Healthy		241 Box Elder	10		Healthy
	Basswood/American	8		Healthy		242 Box Elder	12		Healthy
	Basswood/American	8		Healthy		243 Box Elder 244 Box Elder	12		Healthy
	Basswood/American Elm/American	13 10		Healthy Healthy		244 Box Elder 246 Box Elder	25 8		Healthy Healthy
	Elm/American	9		Healthy		247 Box Elder	8		Healthy
	Elm/American	15		Healthy		248 Box Elder	11		Healthy
	Box Elder	12		Healthy		249 Cottonwood	30		Healthy
106	Box Elder	11		Healthy		251 Box Elder	13		Healthy
107	Box Elder	12		Healthy		254 Box Elder	8		Healthy
108	Cottonwood	28		Healthy		255 Box Elder	12		Healthy
109	Maple/Sugar	15		Healthy		256 Box Elder	8		Healthy
	Maple/Sugar	9		Healthy		258 Box Elder	8		Healthy
	Maple/Sugar	12		Healthy		266 Box Elder	8		Healthy
	Elm/American	16		Healthy		268 Box Elder	23		Healthy
	Box Elder	13		Healthy		270 Box Elder 271 Box Elder	6		Healthy Healthy
	Box Elder Box Elder	14 18		Healthy Healthy		273 Box Elder	12		Healthy
	Box Elder	10		Healthy		275 Box Elder	14		Healthy
	Box Elder	7		Healthy		276 Box Elder	14		Healthy
	Elm/American	17		Healthy		277 Box Elder	13		Healthy
	Box Elder	8		Healthy		279 Box Elder	30		Healthy
135	Box Elder	200		Healthy		280 Box Elder	10		Healthy
136	Box Elder	14		Healthy		284 Willow/Black	33		Healthy
	Box Elder	14		Healthy		285 Cedar/White		11-20	Healthy
	Box Elder	16		Healthy		286 Cedar/White		11-20	Healthy
	Maple/Sugar	8		Healthy		287 Cedar/White		11-20	Healthy
	Box Elder	6		Healthy		288 Cedar/White 289 Birch/Biver		11-20	Healthy
	Elm/American	8		Healthy		289 Birch/River 290 Birch/River	12 10		Healthy Healthy
	Elm/American Box Elder	9 15		Healthy Healthy		290 Birch/River	10		Healthy
	Elm/American	15		Healthy Healthy		291 Birch/River	6		Healthy
	Elm/Siberian	6		Healthy		293 Birch/River	8		Healthy
	Box Elder	6		Healthy		294 Birch/River	10		Healthy
	Box Elder	7		Healthy		296 Birch/River	10		Healthy
				-					

ved

ion Comments

Tree	Deciduos DBH	Conifer Height	Observed Health	
ID # Tree Species	(Inches)	(Feet)	Condition	Comments
297 Box Elder	7		Healthy	
298 Box Elder	6		Healthy	
299 Box Elder	7		Healthy	
300 Box Elder	6		Healthy	
301 Box Elder	15		Healthy	
302 Box Elder	7		Healthy	
303 Box Elder	9		Dead	
304 Birch/River	15		Healthy	
305 Tamarack	10	21-40	Healthy	
306 Birch/River	16		Healthy	
307 Box Elder	6		Healthy	
309 Chokecherry	14		Healthy	

Total # Trees Saved =	170
Total DBH (inches) Saved =	2346
Number of Healthy Trees Saved =	169
Number of Dead or Dying Trees Saved =	1



P.O. BOX 448 VICTORIA, MN 55386 PHONE: (952) 261-9990 WWW.MIDWESTWETLANDS.COM

CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA. Υ.Λ.

Jucius Jonett	
LUCIUS JONETT	

LICENSE NO.: 52856

DA	TE: _		,	10-3	1-20	24		_
ISSUE NO.:	01	02						
DESCRIPTION:	60% PLAN SET	90% PLAN SET						
DATE:	09/09/2024	10/30/2024						

PONDEROSA WOODS STREAN	RESTORATION PROJECT	CITY PROJECT # WR210003
PROJECT TITLE:		
CLIENT:		
P	Plymo	buth
PLYM	Plymouth e Mouth, MN 5 NE: 763-509-{ Plymouthm	5447 5000
PROJECT N	0.:	0017-03
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ
ISSUE DATE	± 1	0/30/2024
ISSUE NO.:		02
SHEET TITL		
TREE S	SURVEY SAVED	
SHEET NO.)4

_	Deciduos Cor		d	Тиро	Deciduos Cor				
Tree ID # Tree Species	DBH Hei (Inches) (Fe	ght Health et) Conditior	n Comments	Tree ID # Tree Species	DBH Hei (Inches) (Fe	ight Health eet) Conditic			
5 Ash/Green	(incries) (i e	Healthy		156 Ash/Green	13	Dead	stump		
7 Cottonwood	30	Healthy		157 Elm/American	6	Healthy	needed for access		
8 Ash/Green	16	Healthy		158 Box Elder 161 Ash/Green	6 21	Healthy Healthy	needed for access		
9 Buckthorn	6	Healthy	C II	162 Ash/Green	23	Healthy			
10 Cottonwood 17 Box Elder	20 14	Dead	fallen fallen	163 Ash/Green	21	Healthy			
18 Cottonwood	25	Dying Dead	fallen	164 Ash/Green	20	Healthy			
21 Box Elder	11	Dying	fallen	168 Ash/Green 169 Ash/Green	23 22	Healthy Healthy			
24 Box Elder	10	Dying	fallen	173 Ash/Green	25	Healthy			
25 Buckthorn	6	Healthy		175 Ash/Green	15	Healthy			
27 Cottonwood	20	Dead	fallen across creek	177 Ash/Green 178 Ash/Green	9 19	Healthy Healthy			
28 Box Elder 29 Cottonwood	9 28	Healthy Healthy		190 Elm/American	6	Dead			
30 Ash/Green	6	Healthy		193 Elm/American	12	Healthy			
31 Ash/Green	12	Dead		194 Ash/Green	12	Healthy	growing next to FES		
32 Cottonwood	25	Dead	fallen	195 Ash/Green 196 Ash/Green	13 16	Healthy Dead	needed for access fallen		
33 Ash/Green	9	Healthy		197 Ash/Green	13	Healthy	Tallett		
34 Box Elder	6	Healthy		198 Box Elder	12	Dead	stump		
35 Cottonwood 38 Box Elder	31 18	Healthy Dead	fallen across creek	199 Box Elder	10	Dead	fallen		
39 Ash/Green	10	Healthy	Tallett act 033 Creek	200 Box Elder 208 Ash/Green	13 12	Dead Dead	fallen fallen		
43 Elm/American	12	Dead		209 Ash/Green	12	Dead	fallen		
44 Buckthorn	6	Healthy		210 Box Elder	15	Dying	fallen		
46 Box Elder	11	Dead	fallen	211 Elm/American	9	Healthy			
47 Box Elder	8	Dead	felles estate	213 Elm/American 214 Cottonwood	11 23	Healthy Dead	fallen		
48 Box Elder	12	Dead	fallen across creek	214 Cottonwood 215 Elm/American	23 16	Dead Healthy			
49 Box Elder 50 Cottonwood	14 33	Dead Healthy		216 Elm/American	15	Dead			
51 Box Elder	12	Dead	fallen	225 Box Elder	15	Dead	fallen across creek		
52 Cottonwood	14	Dead	fallen across creek	227 Box Elder	12	Dead	fallen		
53 Cottonwood	23	Healthy		229 Box Elder 234 Buckthorn	13 8	Dead Healthy			
54 Box Elder	10	Dead	fallen	235 Buckthorn	7	Healthy			
55 Elm/American	11	Healthy		237 Buckthorn	6	Healthy			
56 Elm/American 59 Buckthorn	6	Healthy		238 Buckthorn	8	Healthy	-4		
60 Elm/American	12	Healthy Dead	fallen	239 Cottonwood 240 Buckthorn	27 6	Dead Healthy	stump		
64 Box Elder	26	Dead	fallen across creek	245 Ash/Green	14	Dead	fallen		
65 Box Elder	17	Dead	fallen	250 Buckthorn	6	Healthy			
67 Ash/Green	25	Healthy		252 Buckthorn	7	Healthy			
72 Ash/Green	16	Dead	fallen across creek	253 Buckthorn 257 Ash/Green	6 17	Healthy Dead	fallen		
75 Ash/Green	17	Healthy	fallen	259 Cottonwood	23	Dead	fallen		
77 Basswood/American 78 Ash/Green	25 20	Dead Dead	Talleri	260 Buckthorn	7	Healthy			
80 Ash/Green	28	Healthy		261 Buckthorn	6	Healthy			
82 Maple/Sugar	6	Healthy	growing next to FES	262 Buckthorn 263 Box Elder	15	Healthy Healthy			
86 Ash/Green	10	Healthy		264 Cottonwood	33	Healthy			
88 Elm/American	10	Dead		265 Box Elder	8	Healthy			
90 Maple/Sugar 91 Basswood/American	15 28	Dead Dead	fallen across creek fallen across creek	267 Box Elder 269 Buckthorn	7	Dead Healthy			
94 Maple/Sugar	20	Healthy	Tallell acioss creek	272 Cottonwood	20	Dead	fallen across creek		
95 Ash/Green	14	Dead	fallen across creek	274 Box Elder	13	Dead			
96 Ash/Green	24	Healthy		278 Willow/Black	30	Dead	fallen across creek		
97 Ash/Green	22	Healthy		281 Box Elder 282 Buckthorn	6	Healthy Healthy			
102 Elm/American	15	Healthy		283 Buckthorn	6	Healthy			
110 Box Elder 113 Box Elder	15 12	Healthy Healthy		295 Elm/American	6	Healthy			
114 Elm/American	12	Dead	stump	308 Amur Chokecherry	20	Healthy	amur cherry		
115 Box Elder	13	Dying	stump						
116 Ash/Green	11	Dead	stump						
117 Maple/Sugar	7	Healthy			I # Trees Remov I (inches) Remov				
118 Basswood/American		Healthy		Number of Healt	· ,		2		
119 Hackberry 121 Elm/American	21	Healthy Healthy		Number of Dead or Dyi	•		5		
121 Ein/American 123 Ash/Green	0 14	Healthy							
124 Ash/Green	11	Healthy							
125 Box Elder	13	Healthy							
126 Box Elder	6	Healthy		Tree Rei	moval Summary				
127 Ash/Green	16	Dead		Tree Species # H	Healthy # Dying	or Dead Tota	=		
132 Ash/Green	18 15	Healthy Healthy		Amur Chokecherry	1 C) 1			
138 Ash/Green 139 Buckthorn	15 8	Healthy Healthy		Ash/Green Basswood/American	32 1: 1 2	∠ 44 > ع			
141 Buckthorn	6	Healthy		Basswood/American Box Elder	11 2 ²	4 35			
	13	Dead	fallen	Buckthorn	20 0	20			
142 Box Elder				Cattonwood	6 0	9 15			
142 Box Elder 143 Box Elder	16	Dead	fallen	Cottonwood	40				
142 Box Elder 143 Box Elder 149 Ash/Green	12	Healthy	ralien	Elm/American	10 6	6 16 10 1			
142 Box Elder 143 Box Elder 149 Ash/Green 150 Ash/Green	12 21	Healthy Healthy	raiien	Elm/American Hackberry	10 6 1 0 3 1				
142 Box Elder 143 Box Elder 149 Ash/Green	12	Healthy	raiien	Elm/American	10 6 1 0 3 1 0 1		_		



CERTIFICATION:


I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.


Jucius Jewett	


LICENSE NO.: 52856

DATE:			10-31-2024					
ISSUE NO.:	01	02						
DESCRIPTION:	60% PLAN SET	90% PLAN SET						
DATE:	09/09/2024	10/30/2024						


PONDEROSA WOODS STREAM	RESTORATION PROJECT	CITY PROJECT # WR210003
PROJECT TITLE:		
CLIENT:		
	Plymo	outh
PLYM	Plymouth e Mouth, mn 59 NE: 763-509-5 Plymouthmi	5447 6000
PROJECT N	IO.:	0017-03
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ
ISSUE DATE	≣: 10	0/30/2024
ISSUE NO.:	_	02
	E: SURVEY REMOVE	
SHEET NO.)5








Stream Center Line Profile Sta 2+75 to 5+50




DATE:			 10-3	1-20	24		_
ISSUE NO.:	01	02					
DESCRIPTION:	60% PLAN SET	90% PLAN SET					
DATE:	09/09/2024	10/30/2024					


03
210003
721
¥
1
ECT
0
ЦЦ
≽

900 - RIPRAP CROSS VANE 895 CHANNEL ELEV. = 889.6' - FLOODPLAIN ELEV. = 890.9' DETAIL 1, SHEET C-803 890 885 5+50










TO BE INSTALLED AFTER CONSTRUCTION EXIT

_____ ____ _____. _____ _ _ _ ____ ++++++++++-RIPRAP TOE SILT FENCE _____

LEGEND





MIDWEST WETLAND improvements

P.O. BOX 448 VICTORIA, MN 55386 PHONE: (952) 261-9990 WWW.MIDWESTWETLANDS.COM

CERTIFICATION:


I HEREBY CERTIFY THAT THIS PLAN SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.







AM TRE \mathbf{O} Ш Ś TION PRO S \square **MOO** STORA ONDEROS/ RESTORA Δ

JLIENT:							
Plymouth							
3400 PLYMOUTH BLVD PLYMOUTH, MN 55447 PHONE: 763-509-5000 WWW.PLYMOUTHMN.COM							
PROJECT N	0.:	0017-03					
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ					
ISSUE DATE	: 1()/30/2024					
ISSUE NO.:		02					
SHEET TITL	E:						
CHANNEL STABILIZATION PLAN 2							
	;-11	1					









CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN, I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA. J. A

Jucius Jonett	
LUCIUS JONETT	


52856 LICENSE NO .: _


ATE:	10-31-202


10.:					
ISSUE NO.:	01	02			
:NO	SET	SET			
DESCRIPTION:	60% PLAN SET	90% PLAN SET			
	+	4			
DATE:	09/09/2024	10/30/2024			


PONDEROSA WOODS STREAM	RESTORATION PROJECT	CITY PROJECT # WR210003
PROJECT TITLE:		
CLIENT:		
P	Plymo	buth
PLYM	Plymouth e Iouth, mn 54 NE: 763-509-5 Plymouthmi	5447 5000
PROJECT N	0.:	0017-03
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ
ISSUE DATE	: 10	0/30/2024
ISSUE NO.:		02
SHEET TITLI	E:	
-	NNEL CE	-
SHEET NO.:	;-12	21




















02300 - 31



P.O. BOX 448 VICTORIA, MN 55386 PHONE: (952) 261-9990 WWW.MIDWESTWETLANDS.COM

CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jucius Jonett	
LUCIUS JONETT	


LICENSE NO.: 52856


ATE:	10-31-20
AIL.	10 01 20

		_	_		_	_
ISSUE NO.:	01	02				
DESCRIPTION:	60% PLAN SET	90% PLAN SET				
DATE:	09/09/2024	10/30/2024				

PONDEROSA WOODS STREAM	RESTORATION PROJECT	CITY PROJECT # WR210003
PROJECT TITLE:		
CLIENT:		
P	Plymo	outh
PLYM	Plymouth e 10uth, mn 58 NE: 763-509-5 Plymouthmi	5447 000
PROJECT N	0.:	0017-03
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ
ISSUE DATE	:: 10)/30/2024
ISSUE NO.:	-	02
SHEET TITLI	E: DETAILS	3

SHEET NO.: C-801






-KEY EDGES OF CROSS VANES INTO EXISTING BANKS. AREA AROUND BURIED KEYS TO BE PLANTED WITH 12 SHRUBS, 3 ROWS OF 4, 3' O.C., TYPICAL.


- EXISTING GROUND SURFACE.


2.5' OF CLASS III GRANITE FIELDSTONE RIPRAP.

- 0.75' OF ANGULAR FILTER AGGREGATE.









/ 2.25' OF CLASS III GRANITE FIELDSTONE RIPRAP.


- EXISTING GROUND SURFACE

-0.75' OF ANGULAR FILTER AGGREGATE.

ASS	
III	1
III	
III	
IV	
IV	
IV	

IP R	E) P	IPI

PUBLISHED 1-24 CITY PL. NO. ST-4 REVISED 1-17





CERTIFICATION:

I HEREBY CERTIFY THAT THIS PLAN, I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA. У. Л.

Jucius Jonatt	
LUCIUS JONETT	

LICENSE NO.: 52856

DAT	E: _		1	0-3	1-20	24		_
ISSUE NO.:	01	02						
DESCRIPTION:	60% PLAN SET	90% PLAN SET						
DATE:	09/09/2024	10/30/2024						

PONDEROSA WOODS STREAM	RESTORATION PROJECT	CITY PROJECT # WR210003
PROJECT TITLE:		
CLIENT:		
P	Plymo	outh
PLYM PHON	PLYMOUTH B OUTH, MN 55 NE: 763-509-5 LYMOUTHMN	5447 000
PROJECT NO).:	0017-03
DWN BY: LNJ	CHK'D BY: LNJ	APP'D BY: LNJ
ISSUE DATE:	1()/30/2024
ISSUE NO .:		02
SHEET TITLE		
[DETAILS	6
SHEET NO.:	-80)4